


FOUNTAIN HILLS-13TH PLAT

A TRACT OF LAND IN THE FRACTIONAL NORTHEAST QUARTER OF SECTION 3, TOWNSHIP 51 NORTH, RANGE 33 WEST, OF THE 5TH P.M., IN THE CITY OF KANSAS CITY, CLAY COUNTY, MISSOURI



FINAL PLAT 1 OF 3


LEGEND

- DENOTES SET 1/2" REBAR ALC MO CLS 2022014231
- DENOTES FOUND 1/2" REBAR NO CAP UNLESS NOTED OTHERWISE
- △ DENOTES FOUND SECTION CORNER
- (M) MEASURED
- (P) PLATTED
- (C) CALCULATED
- (D) DEEDED
- POB POINT OF BEGINNING

GENERAL NOTES


- THE BASIS FOR THE BEARING SYSTEM FOR THIS SURVEY IS MISSOURI WEST ZONE U.S. STATE PLANE 1983.
- ALL DISTANCES SHOWN HEREON ARE IN FEET
- REFERENCED SURVEY
- FOUNDATION HILLS, ELEVENTH PLAT INSTRUMENT #2019029032
- FLOODPLAIN NOTE: ACCORDING TO "FIRM" MAP COMMUNITY PANEL NUMBERS 29095C0064G EFFECTIVE JANUARY 20, 2017, AREA ZONE "X" AREA OF MINIMAL FLOOD HAZARD.
- CLOSURE PRECISION: 1 PART IN 2660089.600
- CURRENT ZONING - R-7.5/ R-80
- TITLE COMMITMENT: FILE: FIRST AMERICAN TITLE INSURANCE COMPANY -NCS-1210297-KCTY DATED FEBRUARY 15, 2024 AT 8:00AM

VICINITY MAP



VICINITY MAP
1"=2000'

I DECLARE THAT TO THE BEST OF MY PROFESSIONAL KNOWLEDGE AND BELIEF, THIS PLAT AND SURVEY MEETS THE CURRENT "MISSOURI STANDARD" FOR PROPERTY BOUNDARY SURVEYS (2008-2016).



BRYAN F. HILL

JOB NO:24-032

SCALE

120 60 0 120
SCALE IN FEET

PREPARED FOR

SEC-TWN-RNG

03-51N-33W

FOUNTAIN HILLS HOLDINGS LLC

ADDRESS:
9599 N FOUNTAIN HILLS DR
KANSAS CITY, MO 64155

DATE

NOVEMBER 26, 2024
REVISION DATE: MARCH 31, 2025

Parcel Line and Curve Table

| Line #/Curve # | Length | Bearing/Delta | Radius |
|----------------|---------|---------------|----------|
| C1 | 65.05' | S40°41'47"E | 80.18' |
| C2 | 56.54' | S25°31'38"E | 200.00' |
| C3 | 448.20' | S52°05'46"E | 695.00' |
| C4 | 502.44' | N52°49'37"E | 254.54' |
| C5 | 283.86' | N09°25'40"W | 1425.00' |
| C6 | 46.78' | N21°50'08"W | 200.00' |
| C7 | 101.25' | N14°02'01"W | 200.00' |
| C8 | 17.85' | S16°52'20"W | 200.00' |
| C9 | 106.75' | N70°08'13"W | 225.00' |
| L1 | 68.15' | S17°25'40"E | - |
| L2 | 224.15' | S17°25'40"E | - |
| L3 | 156.01' | S17°25'40"E | - |
| L4 | 169.70' | S33°37'35"E | - |
| L5 | 254.01' | S33°37'35"E | - |
| L6 | 84.32' | S33°37'35"E | - |
| L7 | 117.88' | S70°34'15"E | - |
| L8 | 410.75' | S70°34'15"E | - |
| L9 | 292.87' | S70°34'15"E | - |
| L10 | 178.63' | N15°08'04"W | - |
| L11 | 246.81' | N28°32'12"W | - |
| L12 | 13.13' | N00°28'10"E | - |
| L13 | 115.00' | N72°34'20"E | - |
| L14 | 155.00' | S56°23'32"W | - |
| L15 | 137.17' | S19°25'45"W | - |
| L16 | 90.00' | N83°43'46"W | - |

COUNTY RECORDING INFORMATION

RESERVED FOR COUNTY RECORDING STAMP

PLAT DEDICATION:

FOUNTAIN HILLS-13TH PLAT

PRIVATE OPEN SPACE DEDICATION:

N/A

RECORD AS:


FINAL PLAT


FINAL PLAT DATA TABLE

| Land Data | Area |
|--|-------------|
| Total Land Area | 18.62 Acres |
| Land Area for Proposed and Existing Right of Way | 3.95 Acres |
| Plat Data | Count |
| Number of Lots | 52 Lots |
| Number of Tracts | 3 Tracts |

FOUNTAIN HILLS-13TH PLAT

A TRACT OF LAND IN THE FRACTIONAL NORTHEAST QUARTER OF SECTION 3, TOWNSHIP 51 NORTH, RANGE 33
WEST, OF THE 5TH P.M., IN THE CITY OF KANSAS CITY, CLAY COUNTY, MISSOURI





ALC
ATLAS LAND CONSULTING
SURVEYING | CIVIL ENGINEERING | DRONE | CAD
14500 Parallel Road, Unit R, Basehor KS 66007

FINAL PLAT 2 OF 3


LEGEND

- DENOTES SET 1/2" REBAR ALC MO CLS 2022014231
- DENOTES FOUND 1/2" REBAR NO CAP UNLESS NOTED OTHERWISE
- △ DENOTES FOUND SECTION CORNER
- (M) MEASURED
- (P) PLATTED
- (C) CALCULATED
- (D) DEEDED
- POB POINT OF BEGINNING

GENERAL NOTES


- THE BASIS FOR THE BEARING SYSTEM FOR THIS SURVEY IS MISSOURI WEST ZONE U.S. STATE PLANE 1983
- ALL DISTANCES SHOWN HEREON ARE IN FEET
- REFERENCED SURVEY
- FOUNDATION HILLS, ELEVENTH PLAT INSTRUMENT #2019029032
- FLOODPLAIN NOTE: ACCORDING TO "FIRM" MAP COMMUNITY PANEL NUMBERS 29095C0064G EFFECTIVE JANUARY 20, 2017, AREA ZONE "X" AREA OF MINIMAL FLOOD HAZARD.
- CLOSURE PRECISION: 1 PART IN 2660089.600
- CURRENT ZONING - R-7.5/ R-80
- TITLE COMMITMENT: FILE: FIRST AMERICAN TITLE INSURANCE COMPANY
-NCS-1210297-KCTY DATED FEBRUARY 15, 2024 AT 8:00AM

VICINITY MAP



VICINITY MAP
1"=2000'

I DECLARE THAT TO THE BEST OF MY PROFESSIONAL KNOWLEDGE AND BELIEF, THIS PLAT AND SURVEY MEETS THE CURRENT "MISSOURI STANDARD" FOR PROPERTY BOUNDARY SURVEYS (2008-01-16).




BRYAN F. HILL
2008016658

JOB NO:24-032

| SCALE | PREPARED FOR |
|--|---|
| 80 40 0 80 SCALE IN FEET | FOUNTAIN HILLS HOLDINGS LLC |
| SEC-TWN-RNG | ADDRESS: 9599 N FOUNTAIN HILLS DR KANSAS CITY, MO 64155 |
| 03-51N-33W | |
| DATE | |
| NOVEMBER 26, 2024 REVISION DATE: MARCH 31, 2025 | |

FOUNTAIN HILLS-13TH PLAT

A TRACT OF LAND IN THE FRACTIONAL NORTHEAST QUARTER OF SECTION 3, TOWNSHIP 51 NORTH, RANGE 33 WEST, OF THE 5TH P.M., IN THE CITY OF KANSAS CITY, CLAY COUNTY, MISSOURI



FINAL PLAT 3 OF 3


LEGEND

- DENOTES SET 1/2" REBAR ALC KS CLS 363 MO CLS 2022014231
- DENOTES FOUND 1/2" REBAR NO CAP UNLESS NOTED OTHERWISE
- △ DENOTES FOUND SECTION CORNER
- (M) MEASURED
- (P) PLATTED
- (C) CALCULATED
- (D) DEEDED
- POB POINT OF BEGINNING


GENERAL NOTES

- THE BASIS FOR THE BEARING SYSTEM FOR THIS SURVEY IS MISSOURI WEST ZONE U.S. STATE PLANE 1983.
- ALL DISTANCES SHOWN HEREON ARE IN FEET
- REFERENCED SURVEY
- FOUNDATION HILLS, ELEVENTH PLAT INSTRUMENT #2019029032
- FLOODPLAIN NOTE: ACCORDING TO "FIRM" MAP COMMUNITY PANEL NUMBERS 29095C0064G EFFECTIVE JANUARY 20, 2017, AREA ZONE "X" AREA OF MINIMAL FLOOD HAZARD.
- CLOSURE PRECISION: 1 PART IN 2660089.600
- CURRENT ZONING - R-7.5/ R-80
- TITLE COMMITMENT: FILE: FIRST AMERICAN TITLE INSURANCE COMPANY -NCS-1210297-KCTY DATED FEBRUARY 15, 2024 AT 8:00AM

VICINITY MAP



I DECLARE THAT TO THE BEST OF MY PROFESSIONAL KNOWLEDGE AND BELIEF, THIS PLAT AND SURVEY MEETS THE CURRENT "MISSOURI STATE" PROPERTY BOUNDARY SURVEYING REQUIREMENTS (2019-16).



BRYAN F. HILL PLS-2008016658

JOB NO:24-032

SCALE

PREPARED FOR

SEC-TWN-RNG

03-51N-33W

FOUNTAIN HILLS HOLDINGS LLC

ADDRESS:
9599 N FOUNTAIN HILLS DR
KANSAS CITY, MO 64155

DATE

NOVEMBER 26, 2024
REVISION DATE: MARCH 31, 2025

DESCRIPTION:

PROPERTY DESCRIPTION PER TITLE COMMITMENT FILE NO: NCS-1210297-KCTY
VIA FIRST AMERICAN TITLE INSURANCE COMPANY DATED FEBRUAY 15, 2024 AT 8:00 AM

TRACT 1:
A PORTION OF THE FRACTIONAL NORTHWEST QUARTER OF SECTION 3, TOWNSHIP 51 NORTH, RANGE 33 WEST, IN THE CITY OF KANSAS CITY, CLAY AND PLATTE COUNTIES, MISSOURI, DESCRIBED AS FOLLOWS:
COMMENCING FOR REFERENCE AT THE SOUTHEAST CORNER OF THE SOUTHWEST QUARTER OF SECTION 34, TOWNSHIP 52 NORTH, RANGE 33 WEST, SAID POINT BEING 20.97 FEET WEST OF THE NORTHEAST CORNER OF THE FRACTIONAL NORTHWEST QUARTER OF SAID SECTION 3; THENCE, ALONG THE NORTH LINE OF THE FRACTIONAL NORTHWEST QUARTER OF SAID SECTION 3, SOUTH 89° 44'56" WEST, 314.63 FEET; THENCE, SOUTH 00° 15'04" EAST, 27.72 FEET TO A POINT ON THE APPARENT SOUTH RIGHT OF WAY LINE OF THE 55FOOT WIDE RIGHT-OF-WAY OF NW 96TH STREET, AS EVIDENCED BY THE LONG STANDING OCCUPATION LINES BETWEEN THE ADJACENT PROPERTY OWNERS, WHICH SUPPORTS A 55 FOOT RIGHT-OF-WAY FOR THIS LOCATION, SAID POINT BEING THE TRUE POINT OF BEGINNING; THENCE, SOUTH 00° 15'04" EAST, 2.15 FEET TO A POINT ON THE WESTERLY LINE OF FOUNTAIN HILLS ELEVENTH PLAT, A SUBDIVISION IN CLAY COUNTY, MISSOURI; THENCE, ALONG THE WESTERLY LINE OF FOUNTAIN HILLS ELEVENTH PLAT, THE FOLLOWING THREE (3) COURSES:
1) SOUTH 23° 26'32" WEST, 266.98 FEET TO THE BEGINNING OF A NON-TANGENT CURVE TO THE RIGHT, HAVING AN INITIAL TANGENT BEARING OF SOUTH 66° 33'28" EAST;
2) SOUTHEASTERLY ALONG THE ARC OF LAST SAID CURVE, HAVING A RADIUS OF 975.00 FEET, THROUGH A CENTRAL ANGLE OF 02° 16'32", AN ARC DISTANCE OF 38.72 FEET;
3) SOUTH 25° 43'04" WEST, 158.10 FEET TO A POINT ON THE NORTHERLY LINE OF FOUNTAIN HILLS TENTH PLAT, A SUBDIVISION IN CLAY COUNTY, MISSOURI;
THENCE ALONG THE NORTHERLY LINE OF SAID FOUNTAIN HILLS TENTH PLAT, THE FOLLOWING FOUR (4) COURSES:
1) NORTH 69° 03'35" WEST, 198.26 FEET;
2) NORTH 79° 59'02" WEST, 133.52 FEET;
3) NORTH 86° 00'22" WEST, 199.35 FEET;
4) SOUTH 89° 37'21" WEST, 230.98 FEET TO THE NORTHEAST CORNER OF FOUNTAIN HILLS NINTH PLAT, A SUBDIVISION IN CLAY AND PLATTE COUNTIES, MISSOURI;
THENCE, ALONG THE NORTHERLY LINE OF FOUNTAIN HILLS NINTH PLAT, THE FOLLOWING THIRTEEN (13) COURSES:
1) SOUTH 89° 37'21" WEST, 271.93 FEET;
2) SOUTH 86° 06'51" WEST, 102.16 FEET;
3) SOUTH 79° 27'16" WEST, 140.10 FEET;
4) SOUTH 69° 03'15" WEST, 59.83 FEET;
5) SOUTH 64° 20'21" WEST, 127.23 FEET;
6) SOUTH 39° 23'56" WEST, 8.58 FEET;
7) SOUTH 32° 10'32" WEST, 57.12 FEET;
8) SOUTH 20° 13'48" WEST, 65.66 FEET;
9) NORTH 76° 09'34" WEST, 180.00 FEET TO THE BEGINNING OF A NON-TANGENT CURVE TO THE LEFT, HAVING AN INITIAL TANGENT BEARING OF SOUTH 13° 50'26" WEST;
10) SOUTHERLY ALONG THE ARC OF LAST SAID CURVE, HAVING A RADIUS OF 475.00 FEET, THROUGH A CENTRAL ANGLE OF 05° 29'24", AN ARC DISTANCE OF 45.51 FEET;
11) NORTH 81 °38'58" WEST, 165.27 FEET;
12) NORTH 00° 37'26" WEST, 29.22 FEET;
13) SOUTH 89° 22'34" WEST, 270.02 FEET TO A POINT ON THE EASTERLY LINE OF PLATTE PURCHASE DRIVE AS NOW ESTABLISHED, 60 FEET WIDE;
THENCE, ALONG THE EASTERLY LINE OF SAID PLATTE PURCHASE DRIVE, THE FOLLOWING THREE (3) COURSES:
1) NORTH 00° 32'34" EAST, 212.51 FEET TO THE BEGINNING OF A TANGENT CURVE TO THE RIGHT;
2) NORTHEASTERLY ALONG THE ARC OF LAST SAID CURVE, HAVING A RADIUS OF 505.14 FEET, THROUGH A CENTRAL ANGLE OF 32° 08'19", AN ARC DISTANCE OF 283.35 FEET;
3) NORTH 32° 40'53" EAST, 4.38 FEET TO A POINT ON THE SOUTHERLY RIGHT-OF-WAY LINE OF SAID NW 96TH STREET, 55 FEET WIDE;
THENCE, ALONG SAID SOUTHERLY RIGHT-OF-WAY LINE OF SAID NW 96TH STREET, 55 FEET WIDE, SOUTH 89° 50'05" EAST, 2159.85 FEET TO THE TRUE POINT OF BEGINNING.

TRACT 2:
A PORTION OF THE FRACTIONAL NORTHEAST QUARTER OF SECTION 3, TOWNSHIP 51 NORTH, RANGE 33 WEST, IN THE CITY OF KANSAS CITY, CLAY COUNTY, MISSOURI, DESCRIBED AS FOLLOWS:
COMMENCING FOR REFERENCE AT THE NORTHEAST CORNER OF THE FRACTIONAL NORTHWEST QUARTER OF SAID SECTION3; THENCE ALONG THE NORTH LINE OF THE FRACTIONAL NORTHEAST QUARTER OF SAID SECTION 3, SOUTH 89° 29'00" EAST, 125.01 FEET TO A POINT ON THE EAST LINE OF THE PARCEL DESCRIBED IN THE SPEGAL WARRANTY DEED FILED IN BOOK 6070, PAGE 172, INSTRUMENT NO. 2008038107, SAID POINT BEING THE TRUE POINT OF BEGINNING; THENCE, CONTINUING ALONG THE NORTH LINE OF THE FRACTIONAL NORTHEAST QUARTER OF SAID SECTION 3, SOUTH 89° 29'00" EAST, 703.87 FEET TO THE NORTHWEST CORNER OF THE PARCEL DESCRIBED IN THE WARRANTY DEED FILED IN BOOK 1503, PAGE 600;
THENCE, ALONG THE WESTERLY, SOUTHERLY, AND EASTERLY LINES OF SAID PARCEL DESCRIBED IN BOOK 1503, PAGE 600, THE FOLLOWING THREE (3) COURSES:
1) SOUTH 23° 10'27" EAST, 495.20 FEET;
2) SOUTH 89° 29'00" EAST, 292.90 FEET;
3) NORTH 00° 02'44" WEST, 453.49 FEET TO A POINT ON THE NORTH LINE OF THE FRACTIONAL NORTHEAST QUARTER OF SAID SECTION 3;
THENCE, ALONG THE NORTH LINE OF THE FRACTIONAL NORTHEAST QUARTER OF SAID SECTION 3, SOUTH 89° 29'00" EAST 994.12 FEET TO A POINT ON THE WESTERLY LINE OF MISSOURI STATE HIGHWAY 169; THENCE, ALONG THE WESTERLY LINE OF MISSOURI STATE HIGHWAY 169 AND ALONG THE NORTHERLY LINE OF MISSOURI STATE HIGHWAY 152, THE FOLLOWING FIVE (5) COURSES:
1) SOUTH 06° 15'24" WEST, 140.64 FEET;
2) SOUTH 04° 12'01" EAST, 544.50 FEET;
3) SOUTH 23° 04'17" WEST, 768.06 FEET;
4) SOUTH 60° 33'47" WEST, 654.16 FEET;
5) SOUTH 60° 45'51" WEST, 75.74 FEET TO THE MOST EASTERLY CORNER OF FOUNTAIN HILLS EIGHTH PLAT, A SUBDIVISION IN CLAY COUNTY, MISSOURI;
THENCE, ALONG THE EASTERLY LINE OF FOUNTAIN HILLS EIGHTH PLAT, THE FOLLOWING THREE (3) COURSES:
1) NORTH 29° 08'52" WEST, 36.38 FEET;
2) NORTH 17° 54'57" EAST, 153.61 FEET;
3) NORTH 31° 30'07" WEST, 170.04 FEET TO THE SOUTHEASTERLY CORNER OF FOUNTAIN HILLS ELEVENTH PLAT, A SUBDIVISION IN CLAY COUNTY, MISSOURI;
THENCE, ALONG THE EASTERLY AND NORTHEASTERLY LINES OF FOUNTAIN HILLS ELEVENTH PLAT, THE FOLLOWING NINE (9) COURSES:
1) NORTH 19° 26'38" EAST, 170.39 FEET;
2) NORTH 70° 33'22" WEST, 667.25 FEET;
3) NORTH 58° 40'17" WEST, 148.93 FEET;
4) NORTH 43° 11'09" WEST, 232.64 FEET;
5) NORTH 33° 38'27" WEST, 163.80 FEET;
6) NORTH 33° 37'08" WEST, 213.60 FEET;
7) NORTH 17° 19'45" WEST, 132.69 FEET;
8) NORTH 76° 20'38" WEST, 108.06 FEET;
9) NORTH 89° 29'00" WEST, 0.29 FEET TO THE SOUTHEAST CORNER OF SAID PARCEL DESCRIBED IN BOOK 6070, PAGE 172;
THENCE, ALONG THE EAST LINE OF SAID PARCEL DESCRIBED IN BOOK 6070, PAGE 172, NORTH 00° 10'20" WEST, 348.48 FEET TO THE TRUE POINT OF BEGINNING.

SURVEYORS SUGGESTED LEGAL DESCRIPTION:

A TRACT OF LAND IN THE FRACTIONAL NORTHEAST QUARTER OF SECTION 3, TOWNSHIP 51 NORTH, RANGE 33 WEST, OF THE 5TH P.M., IN THE CITY OF KANSAS CITY, CLAY COUNTY, MISSOURI, BEING PREPARED BY BRYAN F. HILL MO PLS 2008016658, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF SAID FRACTION SECTION 3; THENCE SOUTH 89°29'13" EAST, ALONG THE NORTH LINE OF SAID FRACTIONAL SECTION 3, 123.47 FEET; THENCE SOUTH 00°23'32" EAST, 70.36 FEET TO THE POINT OF BEGINNING OF HEREIN DESCRIBED TRACT; THENCE SOUTH 72°10'02" EAST, 100.58 FEET; THENCE NORTH 89°46'55" EAST, 29.86 FEET; THENCE NORTHEASTERLY, ON A CURVE TO THE LEFT, HAVING AN ARC LENGTH OF 179.99 FEET, A RADIUS OF 1245.92 FEET, A CHORD BEARING OF NORTH 84°5'25" EAST, AND A CHORD LENGTH OF 179.83 FEET; THENCE SOUTH 17°25'40" EAST, 314.74 FEET; THENCE NORTH 72°34'20" EAST, 53.59 FEET; THENCE SOUTH 24°25'14" EAST, 32.04 FEET; THENCE SOUTH 39°37'28" EAST, 245.42 FEET; THENCE SOUTHEASTERLY, ON A CURVE TO THE LEFT, HAVING AN ARC LENGTH OF 328.24 FEET, A RADIUS OF 540.00 FEET, A CHORD BEARING OF SOUTH 52°05'46" EAST, AND A CHORD LENGTH OF 342.24 FEET; THENCE SOUTH 70°34'15" EAST, 394.11 FEET; THENCE NORTHEASTERLY, ON A CURVE TO THE LEFT, HAVING AN ARC LENGTH OF 196.38 FEET, A RADIUS OF 99.49 FEET, A CHORD BEARING OF NORTH 52°47'12" EAST, AND A CHORD LENGTH OF 166.02 FEET; THENCE NORTHWESTERLY, ON A CURVE TO THE LEFT, HAVING AN ARC LENGTH OF 252.99 FEET, A RADIUS OF 1270.03 FEET, A CHORD BEARING OF NORTH 09°25'39" WEST, AND A CHORD LENGTH OF 252.57 FEET; THENCE NORTH 15°08'04" WEST, 145.95 FEET; THENCE SOUTH 89°29'13" EAST, 135.00 FEET; THENCE NORTH 15°08'04" WEST, 69.26 FEET; THENCE NORTHWESTERLY, ON A CURVE TO THE LEFT, HAVGIN AN ARC LENGTH OF 46.72 FEET, A RADIUS OF 174.00 FEET, A CHORD BEARING OF NORTH 22°49'32" WEST, AND A CHORD LENGTH OF 46.57 FEET; THENCE NORTH 28°32'12" WEST, 240.36 FEET; THENCE NORTHWESTERLY, ON A CURVE TO THE RIGHT, HAVING AN ARC LENGTH OF 97.54 FEET, A RADIUS OF 226.00 FEET, A CHORD BEARING OF NORTH 16°10'19" WEST, AND A CHORD LENGTH OF 96.79 FEET TO A POINT ON THE SOUTH RIGHT OF WAY LINE OF NW 96TH STREET AS IT NOW EXISTS; THENCE SOUTH 89°29'13" EAST, ALONG SAID SOUTH RIGHT OF WAY LINE, 50.00 FEET; THENCE SOUTHEASTERLY, ON A CURVE TO THE LEFT, HAVING AN ARC LENGTH OF 71.68 FEET, A RADIUS OF 175.00 FEET, A CHORD BEARING OF SOUTH 16°48'12" EAST, AND A CHORD LENGTH OF 71.18 FEET; THENCE SOUTH 28°32'12" EAST, 239.53 FEET; THENCE SOUTHEASTERLY, ON A CURVE TO THE RIGHT, HAVING AN ARC LENGTH OF 59.20 FEET, A RADIUS OF 225.00 FEET, A CHORD BEARING OF SOUTH 22°44'27" EAST, AND A CHORD LENGTH OF 59.03 FEET; THENCE SOUTH 15°08'04" EAST, 83.82 FEET; THENCE SOUTH 89°29'13" EAST, 244.41 FEET; THENCE SOUTH 00°05'1" WEST, 299.38 FEET; THENCE SOUTH 20°32'14" WEST, 128.60 FEET; THENCE SOUTHEASTERLY, ON A CURVE TO THE RIGHT, HAVING AN ARC LENGTH OF 56.37 FEET, A RADIUS OF 250.00 FEET, A CHORD BEARING OF SOUTH 63°00'13" EAST, AND A CHORD LENGTH OF 56.25 FEET; THENCE SOUTH 33°27'20" WEST, 50.00 FEET; SOUTH 34°26'36" WEST, 213.76 FEET; THENCE SOUTH 51°12'10" WEST, 139.71 FEET; THENCE SOUTH 62°19'19" WEST, 187.93 FEET; THENCE NORTH 70°34'15" WEST, 36.74 FEET TO THE NORTHEAST CORNER OF TRACT A, FOUNTAIN HILLS ELEVENTH PLAT, A SUBDIVISION OF LAND IN THE CITY OF KANSAS CITY, CASS COUNTY, MISSOURI; THENCE NORTH 70°34'15" WEST, ALONG THE NORTH LINE OF SAID TRACT A, 666.74 FEET; THENCE NORTH 58°40'30" WEST, CONTINUING ALONG SAID NORTH LINE, 148.93 FEET; THENCE NORTH 43°11'22" WEST, CONTINUING ALONG SAID NORTH LINE, 232.64 FEET; THENCE NORTH 33°38'40" WEST, CONTINUING ALONG SAID NORTH LINE, 163.80 FEET TO A POINT ON THE NORTH RIGHT OF WAY LINE OF NORTH BELLEVUE AVENUE AS IT NOW EXISTS, ALSO KNOWN TO BE THE SOUTHEAST CORNER OF TRACT B SAID FOUNTAIN HILLS ELEVENTH PLAT; THENCE NORTH 33°40'33" WEST, ALONG THE EAST LINE OF SAID TRACT B, 214.09 FEET; THENCE NORTH 17°18'11" WEST, CONTINUING ALONG SAID EAST LINE, 132.62 FEET TO THE NORTHEASTERLY CORNER OF SAID TRACT B; THENCE NORTH 76°16'57" WEST, ALONG THE NORTH LINE OF SAID TRACT B, 108.06 FEET; THENCE SOUTH 87°29'30" WEST, CONTINUING ALONG SAID NORTH LINE, 0.19 FEET; THENCE NORTH 00°23'32" WEST, 277.78 FEET TO THE POINT OF BEGINNING. CONTAINING 811271.11 SQ FT OR 18.62 ACRES MORE OR LESS

PLAT DEDICATION:

FOUNTAIN HILLS HOLDINGS LLC. ("DEVELOPER") IS OWNER OF ALL REAL ESTATE REFLECTED UPON THIS PLAT AND HAS CAUSED THE SAME TO BE SUBDIVIDED IN THE MANNER SHOWN ON THE PLAT. THE PLAT IS FILED FOR RECORD AND RECORDED SUBJECT TO THE FOLLOWING PROVISIONS, AND THE SUBDIVISION SHALL BE HEREAFTER KNOWN AS: **FOUNTAIN HILLS-13TH PLAT**

EASEMENT DEDICATION:

AN EASEMENT IS HEREBY GRANTED TO KANSAS CITY, MISSOURI, FOR THE PURPOSE OF LOCATING, CONSTRUCTING, OPERATING, AND MAINTAINING FACILITIES FOR WATER, GAS, ELECTRICITY, SEWAGE, TELEPHONE, CABLE TV AND SURFACE DRAINAGE, AND GRADING INCLUDING, BUT NOT LIMITED TO, UNDERGROUND PIPES AND CONDUITS, PAD MOUNTED TRANSFORMERS, SERVICE PEDESTALS , ANY OR ALL OF THEM UPON, OVER, UNDER AND ALONG THE STRIPS OF LAND DESIGNATED UTILITY EASEMENTS (U/E), PROVIDED THAT THE EASEMENT GRANTED HEREIN IS SUBJECT TO ANY AND ALL EXISTING EASEMENTS. ANY UTILITIES LOCATED WITHIN THE DESIGNATED UTILITY EASEMENTS, BY VIRTUE OF THEIR EXISTENCE, DO HEREBY COVENANT, CONSENT, AND AGREE THAT THEY SHALL BE SUBORDINATE TO SAID PUBLIC RIGHT OF WAY IN THE EVENT THAT ADDITIONAL PUBLIC RIGHT OF WAY IS DEDICATED OVER THE LOCATION OF THE UTILITY EASEMENT. WHERE OTHER EASEMENTS ARE DESIGNATED FOR A PARTICULAR PURPOSE, THE USE THEREOF SHALL BE LIMITED TO THAT PURPOSE ONLY. ALL OF THE ABOVE EASEMENTS SHALL BE KEPT FREE FROM ANY AND ALL OBSTRUCTIONS WHICH WOULD INTERFERE WITH THE CONSTRUCTION OR RECONSTRUCTION AND PROPER, SAFE AND CONTINUOUS MAINTENANCE OF THE AFORESAID USES AND SPECIFICALLY THERE SHALL NOT BE BUILT THEREON OR THEREOVER ANY STRUCTURE (EXCEPT DRIVEWAYS, PAVED AREAS, GRASS, SHRUBS AND FENCES) NOR SHALL THERE BE ANY OBSTRUCTION TO INTERFERE WITH THE AGENTS AND EMPLOYEES OF KANSAS CITY, MISSOURI, AND ITS FRANCHISED UTILITIES FROM GOING UPON SAID EASEMENT AND AS MUCH OF THE ADJOINING LANDS AS MAY BE REASONABLY NECESSARY IN EXERCISING THE RIGHTS GRANTED BY THE EASEMENT. NO EXCAVATION OR FILL SHALL BE MADE OR OPERATION OF ANY KIND OF NATURE SHALL BE PERFORMED WHICH WILL REDUCE OR INCREASE THE EARTH COVERAGE OVER THE UTILITIES ABOVE STATED OR THE APPURTENANCES THERETO WITHOUT A VALID PERMIT FROM THE DEPARTMENT OF PUBLIC WORKS AS TO UTILITY EASEMENTS, AND/OR WRITTEN APPROVAL OF THE DIRECTOR OF WATER SERVICES AS TO WATER MAIN EASEMENTS. .

DRAINAGE DEDICATION:

A DRAINAGE EASEMENT (D/E) FOR THE PURPOSE OF STORM WATER DRAINAGE INCLUDING THE RIGHT TO BUILD, CONSTRUCT, KEEP, REPAIR AND MAINTAIN STORM WATER DRAINAGE FACILITIES UNDER, IN, OVER, AND UPON AS MAY BE NECESSARY, BEING AND SITUATED IN KANSAS CITY, MISSOURI ("THE CITY") IS HEREBY GRANTED TO THE CITY. THE CITY SHALL HAVE THE RIGHT AT ALL TIMES TO GO UPON THE LANDS HEREIN DESCRIBED TO CONSTRUCT, MAINTAIN AND REPAIR THE SAID DRAINAGE FACILITIES AS MAY BE NECESSARY. NOTHING SHALL IN ANY WAY INTERFERE WITH THE SAFE AND UNRESTRICTED USE OF THE LAND ADJACENT TO AND ABOVE SAID DRAINAGE FACILITIES, NOR ATTEMPT TO USE SAID PROPERTY IN SUCH MANNER AS WOULD INTERFERE WITH THE PROPER, SAFE AND CONTINUOUS MAINTENANCE AND USE OF SAID DRAINAGE FACILITIES AND SPECIFICALLY SHALL NOT BUILD THEREON OR THEREOVER ANY STRUCTURE WHICH MAY INTERFERE WITH THE MAINTENANCE AND USE THEREOF.

STREET DEDICATION:

STREETS SHOWN HEREON AND NOT HERETOFORE DEDICATED FOR PUBLIC USE AS STREET RIGHT-OF-WAY ARE HEREBY DEDICATED.

BUILDING LINES:

BUILDING LINES OR SETBACK LINES ARE HEREBY ESTABLISHED, AS SHOWN ON THE ACCOMPANYING PLAT, AND NO BUILDING OR PORTION THEREOF SHALL BE BUILT BETWEEN THIS LINE AND THE LOT LINE NEAREST THERETO.

PAYMENT IN LIEU OF PARKLAND:

THE DEVELOPER ELECTS TO PAY THE CITY OF KANSAS CITY, MISSOURI, A SUM OF \$11,499.68 IN LIEU OF REQUIRED PARKLAND DEDICATING FOR 53 SINGLE FAMILY UNITS, PURSUANT TO SECTION 88-408-C OF THE ZONING AND DEVELOPMENT CODE.

IN WITNESS THEREOF:

FOUNTAIN HILLS HOLDING LLC, HAS CAUSED THESE PRESENTS TO BE SIGNED THIS _____ DAY OF _____, 2025.

FOUNTAIN HILLS HOLDING LLC

BY: _____
MANAGING MEMBER

NOTARY CERTIFICATION:

STATE OF ARKANSAS)
)SS
COUNTY OF BENTON)

ON THIS ____ DAY OF _____, 2025, BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC, PERSONALLY APPEARED _____ TO ME KNOWN TO BE THE PERSON DESCRIBED HEREIN AND WHO EXECUTED THE FOREGOING INSTRUMENT AND BEING DULY SWORN BY ME DID ACKNOWLEDGE THAT WALLACE DESIGN COLLECTIVE AND THAT HE EXECUTED THE FOREGOING BY AUTHORITY OF THE BOARD OF DIRECTORS AND IS THE FREE ACT AND DEED OF SAID CORPORATION.

IN WITNESS WHEREOF:

I HAVE HEREUNTO SET MY HAND AND AFFIXED MY NOTARIAL SEAL IN MY OFFICE THE DAY AND YEAR LAST WRITTEN ABOVE.

MY COMMISSION EXPIRES: _____

NOTARY PUBLIC

CITY PLAN COMMISSION:

PUBLIC WORKS:

APPROVED: _____

DIRECTOR OF PUBLIC WORKS

CITY COUNCIL:

THIS IS TO CERTIFY THAT THE WITHIN PLAT WAS DULY SUBMITTED TO AND APPROVED BY THE COUNCIL OF KANSAS CITY, MISSOURI, BY ORDINANCE NO. _____ DULY AUTHENTICATED AS PASSED THIS _____ DAY OF _____, 20____.

MAYOR

CITY CLERK

COUNTY RECORDING INFORMATION

RESERVED FOR COUNTY RECORDING STAMP

PLAT DEDICATION:

FOUNTAIN HILLS-13TH PLAT

PRIVATE OPEN SPACE DEDICATION:

N/A

RECORD AS:

FINAL PLAT

VINCENT E. BRICE
JACKSON COUNTY ASSESSMENT DEPARTMENT